

AD-A105 303 HOSKINS-WESTERN-SONDEREGGER INC LINCOLN NE F/G 13/13  
NATIONAL DAM SAFETY PROGRAM, TRENTON LOWER LAKE DAM (MO 10366),--ETC(U)  
AUG 79 R S DECKER, G ULMER, H P HOSKINS DACW43-79-C-0046

HOSKINS-WESTERN-SONDEREGGER INC LINCOLN NE  
NATIONAL DAM SAFETY PROGRAM, TRENTON LOWER  
AUG 79 R S DECKER, G ULMER, H P HOSKINS

F/G 13/13

NATIONAL DAM SAFETY PROGRAM. TRENTON LOWER LAKE DAM (MO 10366),--ETC(U)  
AUG 79 R S DECKER, G ULMER, H P HOSKINS DACW43-79-C-0046

DACW43-79-C-0046


NL

1 OF  
A1) 6  
106303

END  
DATE  
FILMED  
11-81  
DTIC

**LEVEL II**

**GRAND-CHARITON BASIN**



AN A105303

TRENTON LOWER LAKE DAM

GRUNDY COUNTY, MISSOURI

MO. 10366

**PHASE 1 INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM**

DTIC FILE COPY



United States Army  
Corps of Engineers  
...Serving the Army  
...Serving the Nation

**St. Louis District**

DTIC  
ELECT  
OCT 9 1981  
S D

PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

**DISTRIBUTION STATEMENT A**

Approved for public release;  
Distribution Unlimited

AUGUST, 1979

81 10 7 107

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A105	303
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Trenton Lower Lake Dam (MO 10366) Grundy County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report
7. AUTHOR(s) Hoskins-Western-Sonderegger, Inc.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		8. CONTRACT OR GRANT NUMBER(s) DACW43-79-C-0046
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) National Dam Safety Program. Trenton Lower Lake Dam (MO 10366), Grand - Chariton Basin, Grundy County, Missouri.		12. REPORT DATE August 1979
16. DISTRIBUTION Phase I Inspection Report.		13. NUMBER OF PAGES Approximately 75
Approved for release; distribution unlimited.		15. SECURITY CLASS. (of this report) UNCLASSIFIED
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) H. 13 13/H		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		


DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

TRENTON LOWER LAKE DAM  
GRUNDY COUNTY, MISSOURI  
MO 10366

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

PREPARED BY  
HOSKINS-WESTERN-SONDEREGGER, INC.  
CONSULTING ENGINEERS  
LINCOLN, NEBRASKA

UNDER DIRECTION OF  
ST. LOUIS DISTRICT, CORPS OF ENGINEERS  
FOR

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	

GOVERNOR OF MISSOURI

AUGUST, 1979

DTIC  
ELECTE  
OCT 9 1981  
S D



REPLY TO  
ATTENTION OF

# DEPARTMENT OF THE ARMY

ST. LOUIS DISTRICT, CORPS OF ENGINEERS

210 TUCKER BOULEVARD, NORTH

ST. LOUIS, MISSOURI 63101

SUBJECT: Trenton Lower Lake Dam Phase I Inspection Report

This report presents the results of field inspection and evaluation of the Trenton Lower Lake Dam. It was prepared under the National Program of Inspection of Non-Federal Dams.

SUBMITTED BY: SIGNED 26 MAR 1980  
Chief, Engineering Division Date

APPROVED BY: SIGNED 26 MAR 1980  
Colonel, CE, District Engineer Date

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

TABLE OF CONTENTS

<u>PARAGRAPH NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
	Assessment Summary	
	Overview Photograph	
SECTION 1 - PROJECT INFORMATION		
1.1	General	1
1.2	Description of Project	1
1.3	Pertinent Data	2
SECTION 2 - ENGINEERING DATA		
2.1	Design	5
2.2	Construction	5
2.3	Operation	5
2.4	Evaluation	5
SECTION 3 - VISUAL INSPECTION		
3.1	Findings	6
3.2	Evaluation	9
SECTION 4 - OPERATIONAL PROCEDURES		
4.1	Procedures	10
4.2	Maintenance of Dam	10
4.3	Maintenance of Operating Facilities	10
4.4	Description of Any Warning System in Effect	10
4.5	Evaluation	
SECTION 5 - HYDRAULIC/HYDROLOGIC		
5.1	Evaluation of Features	11
SECTION 6 - STRUCTURAL STABILITY		
6.1	Evaluation of Structural Stability	13
SECTION 7 - ASSESSMENT/REMEDIAL MEASURES		
7.1	Dam Assessment	14
7.2	Remedial Measures	14

## APPENDIX A - MAPS

Plate A-1	Vicinity Topography
Plate A-2	Location Map

## APPENDIX B - PHOTOGRAPHS

Plate B-1	Photo Index	
Plates B-2 to B-5	Photos 2 through 8	South Leg of Dam
Plates B-5 to B-11	Photos 9 through 21	West Leg of Dam
Plates B-12 to B-14	Photos 22 through 27	North Leg of Dam
Plate B-15	Photos 28 and 29	Overviews

## APPENDIX C - PROJECT PLATES

Plate C-1	Phase I - Plan of Dam
Plate C-2	Phase I - Centerline Profiles of North, West and South Legs of Dam
Plate C-3	Phase I - Sections Through North, West and South Legs of Dam
Plate C-4	Phase I - Plan and Profile of Spillway

## APPENDIX D - HYDRAULIC AND HYDROLOGIC DATA

Plates D-1 & D-2	Hydrologic Computations
Plate D-3	Spillway Rating Curve
Plate D-4	Discharge - Ratio Curves
Plates D-5 to D-29	Input and Output for Ratios of PMF



PHASE I REPORT  
NATIONAL DAM SAFETY PROGRAM  
ASSESSMENT SUMMARY

Name of Dam	Trenton Lower Lake Dam
State Located	Missouri
County Located	Grundy County
Stream	Tributary Muddy Creek
Date of Inspection	August 14, 1979

Trenton Lower Lake Dam was inspected by an interdisciplinary team of engineers from Hoskins-Western-Sonderregger, Inc. The purpose of the inspection was to make an assessment of the general conditions of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.

The guidelines used in the assessment were furnished by the Department of the Army, Office of the Chief of Engineers and developed with the help of several Federal and State agencies, professional engineering organizations, and private engineers. Based on these guidelines, this dam is classified as an intermediate size dam with a high downstream hazard potential. Failure would threaten life and property. The estimated damage zone extends approximately one-half mile downstream of the dam. Within the damage zone are 20 or more trailer homes, 2 commercial buildings, Trenton airport with 2 buildings, Trenton Sewage Treatment Plant and an interchange connecting U.S. Highway 65 and Missouri Highway 6.

Our inspection and evaluation indicates that the spillway does not meet the criteria set forth in the recommended guidelines for an intermediate dam having a high hazard potential. The Probable Maximum Flood is the appropriate spillway design flood. The spillway will pass the 100-year flood (flood having a one percent chance of being exceeded in any year) without overtopping the dam. The spillway will pass 55% of the Probable Maximum Flood without overtopping the dam. The Probable Maximum Flood (PMF) is defined as the flood that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region.

It is recommended that the following be pursued on a high priority basis:

- a. Increase the height of dam and/or the size of the spillway

in order to pass the Probable Maximum Flood without overtopping the dam.

b. Engineering studies should be performed to determine the cause, extent and potential effects on structural stability of the apparent slides in the downstream slopes of the dam, and to design protective measures if required.


c. Seepage and stability analyses comparable to the "Recommended Guidelines for Safety Inspection of Dams" should be performed for appropriate loading conditions, including seismic forces, and made a matter of record.

d. Additional studies should be made to determine the hydraulic characteristics of the spillway outlet structure and downstream channel and consequent effects on the integrity of the structure during high discharges through the spillway.


Maintenance has been lax as evidenced by the growth of trees on the slopes, rodent holes in the crest and the uncontrolled growth of sweet clover. Maintenance procedures concerned with the foregoing are recommended in Paragraph 7.2b of this report.



Rey S. Decker  
E-3703



Harold Ulmer  
E-4777



Harold P. Hoskins  
Chairman of Board  
Hoskins-Western-Sonderegger, Inc.  
E-8696



PHOTO NO. 1 OVERVIEW

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
TRENTON LOWER LAKE DAM - MO 10366  
GRUNDY COUNTY, MISSOURI

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

- a. Authority. The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the St. Louis District, Corps of Engineers, District Engineer directed that a safety inspection of Trenton Lower Lake Dam be made.
- b. Purpose of Inspection. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.
- c. Evaluation Criteria. Criteria used to evaluate the dam were furnished by the Department of the Army, Office of the Chief of Engineers, in "Recommended Guidelines for Safety Inspection of Dams," Appendix D to "Report of the Chief of Engineers on the National Program of Inspection of Dams," dated May, 1975, and published by the Department of the Army, Office of the Chief of Engineers.

1.2 DESCRIPTION OF PROJECT

- a. Description of Dam and Appurtenances.
  - (1) The dam is an earth fill approximately 5700 feet in length with a maximum height of about 20 feet. The dam is constructed on three sides of a square and impounds discharges from Trenton Upper Lake. The reservoir covers about 105 acres of nearly level bottomland adjacent to the east side of Muddy Creek on the eastern outskirts of Trenton, Missouri.
  - (2) The spillway consists of an ungated concrete chute with an 8 foot bottom width. The spillway is located in the west leg of the dam some 700 feet north of the

southwest corner of the dam.

(3) Pertinent physical data are given in paragraph 1.3 below.

- b. Location. The dam is located in the central part of Grundy County, Missouri, as shown on Plate A-2. The dam is shown on Plate A-1 in the S $\frac{1}{2}$  of Section 15, T61N, R24W. The lake formed behind the dam is shown in the S $\frac{1}{2}$  of Section 15, T61N, R24W.
- c. Size Classification. Criteria for determining the size classification of dams and impoundments are presented in the guidelines referenced in paragraph 1.1c above. Based on these criteria, this dam and impoundment is in the intermediate size category.
- d. Hazard Classification. Guidelines for determining hazard classification are presented in the same guidelines as referenced in paragraph 1.1c above. Based on these guidelines, this dam is in the High Hazard Classification. The estimated damage zone extends about one-half mile downstream from the dam. Within the damage zone are 20 or more trailer homes, 2 commercial buildings, Trenton Airport with 2 buildings, Trenton Sewage Treatment Plant and an interchange connecting U.S. Highway 65 and Missouri Highway 6.
- e. Ownership. The dam is owned by the White Estate, c/o Mr. Fred Layson, 806 E. 6th, Trenton, Missouri 64683.
- f. Purpose of Dam. Recreation
- g. Design and Construction History. It was reported by Mr. David Blackburn, Trenton City Administrator, that the dam was constructed in 1963 or 1964 by Fred Payne. No other information was available.
- h. Normal Operating Procedure. There are no operating facilities for this dam.

### 1.3 PERTINENT DATA

- a. Drainage Area. 713 acres (1.114 square miles) plus a 1250 acre feet reservoir (Upper Trenton) at the east edge of the lake.
- b. Discharge at Damsite.

- (1) All discharges at the damsite are through an uncontrolled, ungated concrete chute spillway.
- (2) Estimated maximum flood at damsite -- unknown.
- (3) The spillway capacity varies from 0 cfs at its crest elevation 753.4 feet to 142 cfs at elevation 756.8 feet ( minimum top of dam).
- (4) Total spillway capacity at the minimum top of dam is 142 cfs  $\pm$ .

c. Elevations (feet above M.S.L.).

- (1) Top of dam - varies from 756.8 (minimum) to 759.7 (maximum)
- (2) Spillway crest - 753.4 $\pm$
- (3) Streambed at centerline - 740 $\pm$
- (4) Maximum tailwater - unknown

d. Reservoir. Length (feet) of maximum pool - 2,400 $\pm$

e. Storage (Acre-feet).

- (1) Top of dam - 1675 $\pm$
- (2) Spillway crest - 1314 $\pm$

f. Reservoir Surface (Acres).

- (1) Top of dam - 107 $\pm$
- (2) Spillway Crest - 105 $\pm$

g. Dam.

- (1) Type - earth fill
- (2) Length - 5735 feet $\pm$
- (3) Height - varies from 10 feet on the north and south legs to 20 feet on the west leg.
- (4) Top width - 14 to 17 feet
- (5) Side Slopes
  - (a) Downstream - varies from 2 + H on 1V in upper section to 3 + H on 1V in lower (base) section
  - (b) Upstream - varies from 1H on 1V to 1.8 H on 1V
- (6) Zoning - unknown

- (7) Impervious core - unknown
- (8) Cutoff - unknown
- (9) Grout curtain - unknown
- (10) Wave protection - limestone riprap
- (11) Internal drainage system - unknown

h. Diversion Channel and Regulating Tunnel. None

i. Spillway.

- (a) Type - rectangular concrete chute with concrete drop outlet
- (b) Crest (invert) elevation - 753.4 feet  
Outlet - End of chute - 750.4 feet,  
Bottom of outlet box - 743.2 feet
- (c) Length - Control Section - 16 feet  
Chute Section - 33 feet
- (d) Upstream Channel - None, reservoir encroaches on spillway
- (e) Downstream Channel - Natural earth, overgrown with trees and shrubs

j. Regulating Outlets. None

## SECTION 2 - ENGINEERING DATA

### 2.1 DESIGN

No design data were available for this dam.

### 2.2 CONSTRUCTION

No construction data were available. It was reported by Mr. Blackburn that the dam was constructed in 1963 or 1964 by Mr. Fred Payne.

### 2.3 OPERATION

No data were available on spillway operation.

### 2.4 EVALUATION

- a. Availability. No data were available.
- b. Adequacy. The field surveys and visual observations presented herein are considered adequate to support the conclusions of this report. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.
- c. Validity. Not applicable.



## SECTION 3 - VISUAL INSPECTION

### 3.1 FINDINGS

- a. General. A visual inspection of the Trenton Lower Lake Dam was made on August 14, 1979. Engineers from Hoskins-Western-Sonderegger, Inc. Lincoln, Nebraska making the inspection were: R.S. Decker, Geotechnical, and Garold Ulmer, Hydrology. The owner was not represented during the inspection.
- b. Dam.
  1. Geology & Soils (Abutment & Embankment)

This dam is located in the alluvial flood plain of Muddy Creek abutting the bluff line of the adjacent loess-till uplands. The ends (north and south) tie into the till slopes of the upland area. The foundation soils under the embankment appear to be deep alluvial silts and clays (CL) derived from loess and till. The surface two feet of material in the embankment is silty clay (CL).
  2. Upstream Slope. The upstream slope is well riprapped with durable limestone up to about spillway elevation of 754. The area above the riprap is vegetated with vetch and sweet clover. No significant erosion was noted on the upstream slope. A few willow trees are growing on the south and north legs of the dam. The area between Stations 12 + 50 to 13 + 20 ± (south leg) appears to be a slide or slump that has been repaired. No other cracks, slumps or other deformations were noted on the upstream slopes.
  3. Crest - The profiles of the north and south legs of the dam are quite uneven, varying in elevations from 756.8 to 759.7. The profile of the west leg is quite uniform at about elevation 757.5 except for a high spot around the spillway (Sta. 27 + 00 to 28 + 00). The vegetative cover on the south leg (Sta. 0 + 00 - 19 + 00) is quite sparse and consists largely of weeds and vetch. Vegetation on the west leg is sparse (mostly weeds) from Sta. 19 + 00 to the spillway (Sta. 28 + 00). A fair stand of sweet clover covers the remainder of the west leg (to Sta. 40 + 00±). The north leg of the dam is covered with a very dense

growth of sweet clover and weeds (very difficult to walk through) which appears seldom, if ever, mowed. Typical clay drying cracks, 1/8 to 1/4 inches wide, were noted along the crest of most of the south and west legs of the dam. The areas between stations 10 + 15 to 11 + 00± and 12 + 50 to 13 + 20± (south leg) appear to have been repaired at some time. Such repair work could have been necessitated by slides or overtopping; however, there were no indications of recent overtopping. No other significant deformations were noted along the crest. Several rodent holes, up to 4 inches in diameter, were noted along the crest of the south leg (Sta. 2 + 00 to 18 + 00). A few ruts, 1 to 2 inches deep, were noted in the south and west legs of the dam.

4. Downstream Slope. The south leg is sparsely covered with weeds and some grass. Cover on the west leg is primarily weeds and sweet clover. Cover on the north leg consists of dense sweet clover and briars. A few willows and other trees, up to 6 inches in diameter, are growing on the downslopes of the south and north legs of the dam. The downstream slope of the west leg is pretty well covered with shrubs and willow, cottonwood and sycamore trees, up to 8 or 10 inches in diameter. Tree growth is especially heavy between stations 23 + 00 and 26 + 00.
  - (a) South Leg: What appeared to be slump areas that had been repaired were observed downstream from about station 10 + 15 to 11 + 00 (see photo 6) and 12 + 50 to 13 + 20±. These apparent slump areas extend from the crest to about midway down the slope. A 0.5 to 0.75 inch wide crack running longitudinally from about station 16 + 80 to 17 + 10 was observed about midway down the slope. This area appeared to have slumped and been repaired. However, another crack was observed downstream from about station 18 + 00 to 19 + 00 that apparently resulted from poor backfilling of an electrical conduit trench (see photo 8) and the crack between 16 + 80 and 17 + 10 may have resulted from the same activity. No indication of seepage was noted in any of the apparent slump areas nor anywhere else along the downstream slope or toe of the south leg of the dam.
  - (b) West Leg: No cracks were noted along the downstream slope of the west leg.

The possibility of a slide was noted between about station 25 + 50 to 26 + 00 where the lower (basal) half of the slope was much steeper (about 1H on 1V) than other sections of the slope. The only apparent reservoir seepage along the toe of the slope was observed at about station 28 + 50 to 28 + 75. No free water was observed but the area was wet and marshy. Most of the area downstream from (outside) the toe of the dam is wet and marshy. However, this area borders and is the overflow and backwater area for Muddy Creek. In fact, water is ponded just outside the toe of the dam in what appears to be old Muddy Creek channels between about stations 20 + 00 to 23 + 00 and 36 + 00 to 40 + 00 (see Photo 21). Considerable beaver activity was noted around the pond downstream from Sta. 36 + 00 to 40 + 00 but no rodent holes were observed on the dam.

- (c) North Leg: No cracks or rodent holes were observed on the downslope of the north leg, however, the dense vegetative cover made it difficult for such observations. What appeared to be a slump area was observed between stations 53 + 00 to 53 + 50. The apparent slump or slide appeared as an obvious variation in the surface profile of the slope. It extends from the toe up to within 3 or 4 feet of the crest. No seepage was observed in the slide area but it was well vegetated with blue grass and water grasses which were foreign to the vegetative cover on the remainder of the slopes. Water grass was also observed growing 15 to 20 feet outside the toe of the dam from about Station 48 + 00 to the end of the dam (Sta. 57 + 34). However, this area serves as the outfall for surface drainage from the adjacent cultivated land on the north and from the housing development above and on the north end of the dam. A sewer line from the housing development (Upper Trenton Lake Homeowner Association) also follows along the downstream toe of the north leg of the dam. No other signs of seepage were noted on the downstream slope or along the toe of the dam.

5. Miscellaneous. Due to the poor vegetative cover and the presence of what appear to be old slide areas, it is doubtful that the south leg of the dam could withstand overtopping without causing serious damage.

c. Appurtenant Structures.

(1) The spillway consists of an ungated, rectangular concrete chute located at about station 26 + 92 through the west leg of the dam. The chute section is 33 feet in length with a vertical drop of 7.2 feet into a concrete box stilling basin. There are no blocks or other energy dissipators in the outlet box. The concrete structure appears to be in excellent condition. There appeared to be no apparent undercutting of the concrete stilling basin. Several large limestone blocks and boulders occupy the channel just downstream from the outlet box. Some erosion was noted in the earth channel downstream from the rock section but nothing significant.

(2) Drawdown Facilities. No drawdown facilities exist for this dam.

d. Reservoir Area. No significant erosion was noted around the reservoir. The riprapped embankment forms three sides of the lake and most of the remaining (east) side approaches the downstream toe of the Trenton Upper Lake Dam.

e. Downstream Channel. The natural channel downstream from the spillway is overgrown with brush and small trees, but it is doubtful that this growth would cause tailwater problems for the spillway.

3.2 EVALUATION

The stability of the downstream slope appears to be questionable in at least two sections of the south leg (Sta. 10 + 15 to 11 + 00 and 12 + 50 to 13 + 20±), one section of the west leg (Sta. 25 + 50 to 26 + 00) and one section of the north leg (Sta. 53 + 00 to 53 + 50) of the dam. The presence of rodent holes on the south embankment and the uncontrolled growth of trees, especially on the west leg of the dam, could lead to potential of failure of this embankment. The rank growth of sweet clover on the north and portions of the west legs should also be controlled.

Overtopping of this dam, especially the south leg, would probably cause serious damage to the dam and downstream areas.

## SECTION 4 - OPERATIONAL PROCEDURES

### 4.1 PROCEDURES

There are no controlled outlet works for this dam. The pool level is controlled by rainfall, infiltration, evaporation, and the capacity of the uncontrolled spillway.

### 4.2 MAINTENANCE OF DAM

Trees growing on the slopes, rodent holes on the crest, slump/slide areas, and the uncontrolled growth of sweet clover indicate the lack of any regular inspection or maintenance program for this dam.

### 4.3 MAINTENANCE OF OPERATING FACILITIES

No operating facilities exist at this dam.

### 4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

There is no warning system in effect for this dam.

### 4.5 EVALUATION

The lack of regular inspection and maintenance could lead to serious potential of failure of this structure.

## SECTION 5 - HYDRAULIC/HYDROLOGIC

### 5.1 EVALUATION OF FEATURES

- a. Design data. No design data were found for this dam.
- b. Experience Data. The drainage area, reservoir surface area, and elevation-storage data were developed from the USGS Trenton, Missouri 15 minute topographic quadrangle map. The hydraulic computations for the spillway and dam overtopping discharge ratings were based on data collected in the field at the time of the field inspection.
- c. Visual Observations.
  - (1) The Upper Trenton Dam spillway releases directly into the reservoir of the Lower Trenton Dam. The tailwater of the lower reservoir encroaches upon the downstream toe of the upper dam.
  - (2) Spillway appears to be in good condition. No trash or debris was found in the spillway entrance.
  - (3) There was some slight erosion in the earth channel downstream from the spillway. The channel was overgrown with weeds and small trees.
- d. Overtopping Potential. The spillway is too small to pass the probable maximum flood without overtopping. The spillway will pass approximately 55% of the probable maximum flood without overtopping the dam. The spillway will pass the 100-year frequency flood without overtopping the dam. Overtopping of the dam would probably cause significant damage to the dam. The results of the routings through the dam are tabulated in regards to the following conditions:

<u>Frequency</u>	<u>Inflow Discharge c.f.s.</u>	<u>Outflow Discharge c.f.s.</u>	<u>Maximum Pool Elevation</u>	<u>Freeboard Top of Dam Min. Elev. 756.8</u>	<u>Time Dam Overtopping Hr.</u>
0.5 PMF	2200	90	755.9	+0.9	0
PMF	5100	4300	757.9	-1.1	8+
0.55 PMF	2500	140	756.8	0	0

According to the recommended guidelines from the Department of the Army, Office of the Chief of Engineers, this dam is classified as having a high hazard rating and an intermediate size. Therefore, the PMF is the test for the adequacy of the dam and its spillway.

The estimated damage zone is described in Paragraph 1.2d of this report.

## SECTION 6 - STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

- a. Visual Observation. In light of the apparent slides and/or slumps on the downstream slopes, the structural stability of sections of the embankment appears to be questionable. Large trees and rodent holes in the embankment could impair the structural stability of the dam. The effects of overtopping on structural and erosional stability are not known. The amount and extent of erosion that might be caused by high discharges through the spillway and the resultant effects upon the integrity of the structure are not known.
- b. Design and Construction Data. No design or construction data were available. Seepage and stability analyses were not available, which is considered a deficiency.
- c. Operating Records. There are no controlled operating facilities for this dam.
- d. Post Construction Changes. The inspection team is not aware of any significant post construction changes on this dam. The shallow installation of electrical conduit on a short section of the downstream slope of the south leg and the installation of the sewer line along the toe of the north leg were performed after the dam was constructed. Neither installation should have a significant effect upon performance of the structure.
- e. Seismic Stability. This dam is located in Seismic Zone 1. An earthquake of the magnitude predicted in this area is not ordinarily expected to cause structural failure of a dam of this height and character. However, due to the apparent slides and/or slumps in downstream sections of this dam, seismic forces should be included in stability analyses of the structure.



## SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

### 7.1 DAM ASSESSMENT

- a. Safety. The structural stability of this dam appears to be questionable. Seepage and stability analyses were not available which is considered a deficiency. Deficiencies in maintenance (trees on slopes, rodent holes, etc.) could ultimately increase the potential of failure of the embankment.

Based upon the approximate data available for analyses, the dam will not be overtopped by the 100-year nor the 50% PMF storms. The PMF (spillway design storm) will overtop the dam by about 1 foot and a breach failure of Upper Trenton Dam would probably overtop this dam by several feet.

Erosion of the outlet end of the spillway could impair the integrity of the spillway structure.

- b. Adequacy of Information. Due to the lack of engineering data, the conclusions in this report are based upon performance history and visual observations. Seepage and stability analyses comparable to the requirements of the guidelines were not available which is considered a deficiency.
- c. Urgency. The analyses and remedial measures recommended in paragraph 7.2 should be pursued on a high priority basis.
- d. Necessity for Phase II. Phase II investigation is not considered necessary. However, the additional studies and analyses recommended in paragraph 7.2 should be accomplished in the near future.
- e. Seismic Stability. This dam is located in Seismic Zone 1. An earthquake of this magnitude is not ordinarily expected to be hazardous to a dam of this height and character. Due to the presence of apparent slides in the downstream slopes of this dam, seismic forces should be included in analyzing the stability of this structure.

### 7.2 REMEDIAL MEASURES

- a. Alternatives.

- (1) Additional information should be obtained on the topographic characteristics of the reservoir area


to determine the increase in the height of dam or the size of the spillway that is necessary to pass the Probable Maximum Flood or the flood that could result from failure of Upper Trenton Dam without overtopping the dam.


- (2) Additional studies should be performed to determine the cause, extent and potential effects on structural stability of the apparent slides in the downstream slopes of the dam.
- (3) Seepage and stability analyses comparable to the "Recommended Guidelines for Safety Inspection of Dams" should be performed by a professional engineer experienced in the design and construction of dams for appropriate loading conditions including seismic forces, and made a matter of record.
- (4) Additional studies should be made to determine the hydraulic characteristics of the spillway outlet structure and downstream channel and consequent effects on the integrity of the structure during high discharges through the spillway.
- (5) The services of an engineer experienced in the design and construction of earth dams should be obtained to perform the above studies, analyses and evaluations and to design protective measures, if required.

b. O & M Procedures.

- (1) Seepage and stability analyses should be performed by a professional engineer experienced in the design and construction of earth dams.
- (2) Trees should be removed from the slopes of the dam and measures taken to prevent their recurrence. Removal of large trees should be done under the guidance of an engineer experienced in the design and construction of earth dams.
- (3) Rodent holes on the crest and slopes of the embankment should be repaired.
- (4) A program of periodic inspection and maintenance should be initiated to control tree and other vegetative growth and rodent activity on the dam and other deficiencies that could affect the stability and/or performance of the structure.

APPENDIX A  
MAPS





APPENDIX B  
PHOTOGRAPHS




PLATE B-1



PHOTO NO. 2 CREST OF SOUTH LEG TAKEN FROM EAST END



PHOTO NO. 3 UPSTREAM SLOPE OF SOUTH LEG





PHOTO NO. 4 DOWNSTREAM SLOPE TAKEN FROM STA. 7+00  
LOOKING WEST



PHOTO NO. 5 DOWNSTREAM SLOPE TAKEN FROM STA. 7+00  
LOOKING EAST



PHOTO NO. 6 SLUMP AREA FROM STA. 10+15 TO 11+00.  
TREES GROWING IN SLUMP AREA



PHOTO NO. 7

LONGITUDINAL CRACK  
STA. 16+80 TO 17+10



PHOTO NO. 8 CRACK AND EROSION RESULT OF INSTALLATION  
OF UNDERGROUND POWER LINE



PHOTO NO. 9 UPSTREAM SLOPE OF WEST LEG TAKEN FROM  
STA. 18+25



PHOTO NO. 10 CREST OF WEST LEG LOOKING NORTH FROM  
STA. 21+00



PHOTO NO. 11 DOWNSTREAM SLOPE OF WEST LEG FROM  
STA. 21+00 LOOKING NORTH



PHOTO NO. 12 UPSTREAM ACROSS LAKE FROM STA. 22+25



PHOTO NO. 13 DOWNSTREAM SLOPE FROM STA. 25+50 TO  
SOUTH. 2H TO 1V SLOPE FROM MIDWAY UP  
SLOPE TO TOE



PHOTO NO. 14 VIEW OF SPILLWAY FROM DOWNSTREAM CHANNEL



PHOTO NO. 15 VIEW OF SPILLWAY DROP STRUCTURE



PHOTO NO. 16 VIEW UPSTREAM IN SPILLWAY FROM DROP  
STRUCTURE



PHOTO NO. 17 VIEW DOWNSTREAM IN SPILLWAY




PHOTO NO. 18 CREST OF WEST LEG LOOKING NORTH FROM  
SPILLWAY



PHOTO NO. 19 VIEW DOWNSTREAM FROM STA. 30+00





PHOTO NO. 20 UPSTREAM FROM STA. 30+00



PHOTO NO. 21 POND AT TOE OF WEST LEG. STA. 36+00  
TO 40+00



PHOTO NO. 22 UPSTREAM SLOPE OF NORTH LEG TAKEN  
FROM STA. 36+00 ON WEST LEG



PHOTO NO. 23 DOWNSTREAM SLOPE OF NORTH LEG TAKEN  
FROM WEST LEG




PHOTO NO. 24 UPSTREAM SLOPE OF WEST LEG TAKEN  
FROM NORTH LEG



PHOTO NO. 25 UPSTREAM SLOPE OF NORTH LEG LOOKING WEST



PHOTO NO. 26 UPSTREAM SLOPE OF NORTH LEG LOOKING EAST



PHOTO NO. 27 CREST OF NORTH LEG TAKEN FROM EAST END




PHOTO NO. 28 OVERVIEW TAKEN FROM TRENTON UPPER LAKE DAM




PHOTO NO. 29 OVERVIEW TAKEN FROM TRENTON UPPER LAKE DAM


APPENDIX C  
PROJECT PLATES




PLAN  
Scale: 1" = 400'



**E PROFILE - NORTH LEG OF DAM CREST**




**E PROFILE - WEST LEG OF DAM CREST**



**E PROFILE - SOUTH LEG OF DAM CREST**

Scale: 1" = 250' H.  
1" = 5' V.






SECTION AT STA. 17+00 (SOUTH)

Scale: 1" = 20' H.


1" = 10' V.



SECTION AT STA. 22+25 (WEST)

Scale: 1" = 20' H.



1" = 10' V.



SECTION AT STA. 42+25 (NORTH)

Scale: 1" = 20' H.

1" = 10' V.




APPENDIX D  
HYDRAULIC AND HYDROLOGIC DATA

## HYDROLOGIC COMPUTATIONS

1. The SCS dimensionless unit hydrograph and the systemized computer program HEC-1 (Dam Safety Version), July 1978, prepared by the Hydrologic Engineering Center, U.S. Corps of Engineers, Davis, California, were used to develop the inflow hydrographs.
  - a. Twenty-four hour, 100-year rainfall for the dam location was taken from the data for the rainfall station at Maryville, MO. as supplied by the St. Louis District, Corps of Engineers per their letter dated March 6, 1979. The twenty-four hour probable maximum precipitation was taken from the curves of the Hydrometeorological Report No. 33 and current Corps of Engineers and St. Louis District policy and guidance for hydraulics and hydrology.
  - b. Drainage area = 1.114 square miles (713 acres).
  - c. Time of concentration of runoff = (See paragraph 1.g of this Section.)
  - d. The antecedent storm conditions for the probable maximum precipitation were heavy rainfall and low temperatures which occurred on the previous 5 days (SCS AMC III). The antecedent storm conditions for the 100-year precipitation were an average of the conditions which have preceded the occurrence of the maximum annual flood on numerous watersheds (SCS AMC II). The initial pool elevation was assumed at the invert of the spillway.
  - e. The total twenty-four hour storm duration losses for the 100-year storm were 1.64 inches. The total losses for the PMF storm were 0.75 inches. These data are based on SCS runoff curve No. 94 and No. 86 for antecedent moisture conditions SCS AMC III and AMC II respectively. The watershed consists of the Upper Trenton Lake's watershed, the downstream slope of the Upper Trenton Dam and the Lower Trenton reservoir. The Upper Trenton watershed consists of soils from SCS soil groups C and D with land usage made up of cropland and urban areas with some woods.
  - f. Average soil loss rates = 0.03 inch per hour approximately (for PMF storm, AMC III).

- g. The inflow hydrograph for the reservoir was composed of two components. The rainfall on the lower reservoir and the downstream slope of the Upper Trenton Dam was converted into direct runoff and combined with the outflow hydrograph from the Upper Trenton Dam to produce the inflow hydrograph for the Lower Trenton Dam.
- 2. The combined discharge rating consisted of two components: the flow through the spillway and the flow going over the top of the dam.
  - a. The spillway ratings were developed using the Corps of Engineers Water Surface Profile HEC-2 computer program.
  - b. The flows over the dam were developed using the dam overtopping analysis (irregular dam top) within the HEC-1 (Dam Safety Version) program.
- 3. Floods were routed through the reservoir using the HEC-1 (Dam Safety Version) program to determine the capabilities of the spillway and dam embankment crest. The Upper Trenton Dam and Lower Trenton Dam were routed in series due to the fact that the Upper Trenton Dam discharges directly into the Lower Trenton reservoir. The input-output for several ratios of the PMF and the plotted hydrograph for the PMF are attached in this Appendix.



LOWER TRENTON DAM  
NO. 103566




PLATE D-5





PREVIEW 11 SEQUENCE OF STREAM NETWORK CALCULATIONS

ROUTE HYDROGRAPH AT 000001  
ROUTE HYDROGRAPH TO 000002  
ROUTE HYDROGRAPH AT 000003  
COMPLETE 2 HYDROGRAPHS AT M 2+3  
ROUTE HYDROGRAPH TO 000034  
END OF NETWORK

CFS 5157. 1950. 537. 587. 163929.  
 CMS 146. 52. 17. 17. 4784.  
 INCHES 19.12 24.25 24.25 24.25  
 PM 485.71 615.96 615.96 615.96  
 AC-FI 917. 4163. 4163. 4163.  
 THOUS CU F 1132. 1439. 1439. 1439.

# HYDROGRAPH AT STAG0001 FOR PLAN 1, RHO 9 **PMF**

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME  
 CFS 2313. 733. 733. 211161.  
 CMS 65. 21. 21. 5979.  
 INCHES 23.90 30.31 30.31 30.31  
 PM 607.14 769.95 769.95 769.95  
 AC-FI 1147. 1454. 1454. 1454.  
 THOUS CU F 1415. 1796. 1796. 1796.

\*\*\*\*\*

## HYDROGRAPH ROUTING

### ROUTED FLOODS (DOU RES. 10365)

STAGE	ICOMP	REGON	ITAPE	JPLT	JPRE	INAME	ISTAGE	IAUTO
000002	1	0	0	2	0	I	0	0
GLUSS	AVG	IPES	ISAME	IUPI	IPMP		ISTR	
0.0	0.000	0.00	1	0	0		0	
NSIPS	HSIDR	LAS	ARSKR	K	ISK	SIORA	ISPRAT	
1	0	0	0.000	0.000	0.000	-704.	-1	

STAGE	ICOMP	REGON	ITAPE	JPLT	JPRE	INAME	ISTAGE	IAUTO
735.50	785.00	780.00	767.00	787.00	789.00	799.00	790.00	790.00
0.00	0.00	33.00	57.00	73.00	86.00	92.00	92.00	110.00
0.	170.	330.	465.	689.	920.	970.	1150.	1540.
ELEVATION	763.	775.	780.	786.	786.	789.	790.	792.

CRTI	STAGE	ICOMP	REGON	ITAPE	JPLT	JPRE	INAME	ISTAGE	IAUTO
785.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	

### DAM DATA

LOPEL	COUO	EXPD	DAPRHO
791.0	2.9	1.5	1145.

LOPEL	COUO	EXPD	DAPRHO
0.	110.	225.	570.
791.0	792.1	792.5	792.7
			793.1
			793.3

STATION 080002, PLAN 1, PAFIC 1

\*\*\*\*\*

STATION 000002, PLAN 1, RATE 9  
PMF

## END-OF-PERIOD HYDROGRAPH ORIGINATES

[illegible][illegible]



STAT10000002

	0.	1000.	2000.	3000.	4000.	5000.	6000.	7000.	0.	0.	0.	0.	0.	0.
05														
11														
10														
21														
15														
31														
51														
51														
61														
61														
71														
81														
81														
91														
101														
111														
121														
131														
141														
151														
161														
171														
181														
191														
201														
211														
221														
231														
241														
251														
261														
271														
281														
291														
301														
311														
321														
331														
341														
351														
361														
371														
381														
391														
401														
411														
421														
431														
441														
451														
461														
471														
481														
491														
501														
511														
521														
531														
541														
551														
561														

6.55 5701	6.55 5701
6.55 5301	6.55 5301
6.55 5401	6.55 5401
6.55 6001	6.55 6001
6.55 6101	6.55 6101
6.55 6201	6.55 6201
6.55 6301	6.55 6301
6.55 6401	6.55 6401
6.55 6501	6.55 6501
6.55 6601	6.55 6601
6.55 6701	6.55 6701
6.55 6801	6.55 6801
6.55 6901	6.55 6901
6.55 7001	6.55 7001
6.55 7101	6.55 7101
6.55 7201	6.55 7201
6.55 7301	6.55 7301
6.55 7401	6.55 7401
6.55 7501	6.55 7501
6.55 7601	6.55 7601
6.55 7701	6.55 7701
6.55 7801	6.55 7801
6.55 7901	6.55 7901
6.55 8001	6.55 8001
6.55 8101	6.55 8101
6.55 8201	6.55 8201
6.55 8301	6.55 8301
6.55 8401	6.55 8401
6.55 8501	6.55 8501
6.55 8601	6.55 8601
6.55 8701	6.55 8701
6.55 8801	6.55 8801
6.55 8901	6.55 8901
6.55 9001	6.55 9001
6.55 9101	6.55 9101
6.55 9201	6.55 9201
6.55 9301	6.55 9301
6.55 9401	6.55 9401
6.55 9501	6.55 9501
6.55 9601	6.55 9601
6.55 9701	6.55 9701
6.55 9801	6.55 9801
6.55 9901	6.55 9901
6.55 10001	6.55 10001
6.55 10101	6.55 10101
6.55 10201	6.55 10201
6.55 10301	6.55 10301
6.55 10401	6.55 10401
6.55 10501	6.55 10501
6.55 10601	6.55 10601
6.55 10701	6.55 10701
6.55 10801	6.55 10801
6.55 10901	6.55 10901
6.55 11001	6.55 11001
6.55 11101	6.55 11101
6.55 11201	6.55 11201
6.55 11301	6.55 11301
6.55 11401	6.55 11401
6.55 11501	6.55 11501
6.55 11601	6.55 11601
6.55 11701	6.55 11701
6.55 11801	6.55 11801
6.55 11901	6.55 11901
6.55 12001	6.55 12001

10.51100  
 10.501200  
 10.51210  
 10.101220  
 10.151230  
 10.201240  
 10.251250  
 10.301260  
 10.351270  
 10.401280  
 10.451290  
 10.501300  
 10.551310  
 10.601320  
 10.651330  
 10.701340  
 10.751350  
 10.801360  
 10.851370  
 10.901380  
 10.951390  
 11.001400  
 11.051410  
 11.101420  
 11.151430  
 11.201440  
 11.251450  
 11.301460  
 11.351470  
 11.401480  
 11.451490  
 11.501500  
 11.551510  
 11.601520  
 11.651530  
 11.701540  
 11.751550  
 11.801560  
 11.851570  
 11.901580  
 11.951590  
 12.001600  
 12.051610  
 12.101620  
 12.151630  
 12.201640  
 12.251650  
 12.301660  
 12.351670  
 12.401680  
 12.451690  
 12.501700  
 12.551710  
 12.601720  
 12.651730  
 12.701740  
 12.751750  
 12.801760  
 12.851770  
 12.901780  
 12.951790  
 13.001800






PLATE D-14

20.15243.1	0
20.20244.1	0
20.25245.1	0
20.30246.1	0
20.35247.1	0
20.40248.1	0
20.45249.1	0
20.50250.1	0
20.55251.1	0
21.00252.1	0
21.05253.1	0
21.10254.1	0
21.15255.1	0
21.20256.1	0
21.25257.1	0
21.30258.1	0
21.35259.1	0
21.40260.1	0
21.45261.1	0
21.50262.1	0
21.55263.1	0
22.00264.1	0
22.05265.1	0
22.10266.1	0
22.15267.1	0
22.20268.1	0
22.25269.1	0
22.30270.1	0
22.35271.1	0
22.40272.1	0
22.45273.1	0
22.50274.1	0
22.55275.1	0
23.00276.1	0
23.05277.1	0
23.10278.1	0
23.15279.1	0
23.20280.1	0
23.25281.1	0
23.30282.1	0
23.35283.1	0
23.40284.1	0
23.45285.1	0
23.50286.1	0
23.55287.1	0
24.00288.1	0

CONVERSION OF DIRECT RAINFALL UN RES 10366 TO CFS

[illegible]

HYDROGRAPH AT STA00003 FOR PLAN 1, RTIO 6 **0.5 PMF**

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2153.	200.	89.	89.	25570.
CMS	61.	8.	3.	3.	724.
INCHES		12.17	15.44	15.44	15.44
MM		308.99	392.11	392.11	392.11
AC-FT		139.	176.	176.	176.
THOUS CU M		171.	217.	217.	217.

HYDROGRAPH AT STA00003 FOR PLAN 1, RTIO 7

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2799.	364.	115.	115.	33241.
CMS	79.	10.	3.	3.	941.
INCHES		15.81	20.07	20.07	20.07
MM		401.69	509.75	509.75	509.75
AC-FT		180.	229.	229.	229.
THOUS CU M		223.	282.	282.	282.

HYDROGRAPH AT STA00003 FOR PLAN 1, RTIO 8

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	3445.	448.	142.	142.	40912.
CMS	98.	13.	4.	4.	1158.
INCHES		17.46	24.70	24.70	24.70
MM		494.39	627.38	627.38	627.38
AC-FT		222.	282.	282.	282.
THOUS CU M		274.	348.	348.	348.

HYDROGRAPH AT STA00003 FOR PLAN 1, RTIO 9 **PMF**

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	4307.	560.	178.	178.	51140.
CMS	122.	16.	5.	5.	1448.
INCHES		24.33	30.87	30.87	30.87
MM		617.90	784.22	784.22	784.22
AC-FT		278.	352.	352.	352.
THOUS CU M		342.	434.	434.	434.

COMBINE HYDROGRAPHS						
INFLW HYDRO TO RLS 10366						
ESTAC	ICOMP	TECON	TTAPE	JPLT	JPRI	ISTAGE
P 2+3	2	0	0	2	0	0
SEP OF 2 HYDROGRAPHS AT M 2+3 PLAN 1 RTIO 1						

CHV16

SUM OF 2 HYDROGRAPHS AT M 213 PLAN 1 RT10 9

PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
5182.	1932.	606.	606.	114532.
144.	55.	17.	17.	4942.
	16.13	20.24	20.24	20.24
	404.68	514.14	514.14	514.14
	958.	1202.	1202.	1202.
	1181.	1483.	1483.	1483.

CFS  
CMS  
INCHES  
AC-FT  
THOUS CU F

[illegible]

НАУЧНО-ИССЛЕДОВАТЕЛЬСКИЙ

ROUTED FLOWS (HR) KFS 10366

STAGE	FLUX	QLOSS	CLUSS	CLUSS	ICUMIP	ICURN	ITAPE	JPLT	JORT	INAME	ISTAGE	IAUTO
		0.0	0.000	0.000	1	0	0	2	0	1	0	0
				AVG			ROUTING DATA					
							IRSS	ISAML	LOPT	IPMP	LSTR	
							1	1	0	0	0	
				NSIPS	NSIDL	LAG	ANSKK	X	TSK	STORA	ISPRAT	
				1	0	0	0.000	0.000	0.000	-753.	-1	
		754.00					754.60	755.10	756.10		757.00	758.00
		10.00		20.00			30.00	50.00	100.00		150.00	182.00

CREL	SPWID	CUQW	EXPM	ELEV	COQL	CAREA	EXPL
753.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM DATA			
TOUPL	COUD	EXPD	DAMPID
756.8	2.9	1.5	4190.

CREST LEATH AT OR BELOW ELEVATION	100.	470.	640.	1130.	1820.	2830.	3530.	4190.
	756.0	757.0	757.1	757.3	757.4	757.6	757.7	758.0

STATION 00000, PLAN 1, RATIO 1

# END-OFF-PERIOD HYDROGRAPH URGINATES

[illegible]

STATION 000004, PLAN 1, RATIC 9  
END-OF-PERIOD HYDROGRAPH ORDINATES

[illegible]

4305. AT TIME 16.67 HOURS

PLATE D-21



DATE

STATION 000004

	0.	1000.	2000.	3000.	4000.	5000.	6000.	0.	0.	0.	0.	0.	0.	0.
.05 11	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.10 21	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.15 31	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.20 41	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.25 51	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.30 61	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.35 71	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.40 81	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.45 91	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.50 101	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.55 111	.	.	.	.	.	.	.	.	.	.	.	.	.	.
1.00 121	.	.	.	.	.	.	.	.	.	.	.	.	.	.
1.05 131	.	.	.	.	.	.	.	.	.	.	.	.	.	.
1.10 141	.	.	.	.	.	.	.	.	.	.	.	.	.	.
1.15 151	.	.	.	.	.	.	.	.	.	.	.	.	.	.
1.20 161	.	.	.	.	.	.	.	.	.	.	.	.	.	.
1.25 171	.	.	.	.	.	.	.	.	.	.	.	.	.	.
1.30 181	.	.	.	.	.	.	.	.	.	.	.	.	.	.
1.35 191	.	.	.	.	.	.	.	.	.	.	.	.	.	.
1.40 201	.	.	.	.	.	.	.	.	.	.	.	.	.	.
1.45 211	.	.	.	.	.	.	.	.	.	.	.	.	.	.
1.50 221	.	.	.	.	.	.	.	.	.	.	.	.	.	.
1.55 231	.	.	.	.	.	.	.	.	.	.	.	.	.	.
2.00 241	.	.	.	.	.	.	.	.	.	.	.	.	.	.
2.05 251	.	.	.	.	.	.	.	.	.	.	.	.	.	.
2.10 261	.	.	.	.	.	.	.	.	.	.	.	.	.	.
2.15 271	.	.	.	.	.	.	.	.	.	.	.	.	.	.
2.20 281	.	.	.	.	.	.	.	.	.	.	.	.	.	.
2.25 291	.	.	.	.	.	.	.	.	.	.	.	.	.	.
2.30 301	.	.	.	.	.	.	.	.	.	.	.	.	.	.
2.35 311	.	.	.	.	.	.	.	.	.	.	.	.	.	.
2.40 321	.	.	.	.	.	.	.	.	.	.	.	.	.	.
2.45 331	.	.	.	.	.	.	.	.	.	.	.	.	.	.
2.50 341	.	.	.	.	.	.	.	.	.	.	.	.	.	.
2.55 351	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3.00 361	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3.05 371	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3.10 381	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3.15 391	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3.20 401	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3.25 411	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3.30 421	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3.35 431	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3.40 441	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3.45 451	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3.50 461	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3.55 471	.	.	.	.	.	.	.	.	.	.	.	.	.	.
4.00 481	.	.	.	.	.	.	.	.	.	.	.	.	.	.
4.05 491	.	.	.	.	.	.	.	.	.	.	.	.	.	.
4.10 501	.	.	.	.	.	.	.	.	.	.	.	.	.	.
4.15 511	.	.	.	.	.	.	.	.	.	.	.	.	.	.
4.20 521	.	.	.	.	.	.	.	.	.	.	.	.	.	.
4.25 531	.	.	.	.	.	.	.	.	.	.	.	.	.	.
4.30 541	.	.	.	.	.	.	.	.	.	.	.	.	.	.
4.35 551	.	.	.	.	.	.	.	.	.	.	.	.	.	.
4.40 561	.	.	.	.	.	.	.	.	.	.	.	.	.	.

4.55 571  
 4.50 581  
 4.55 591  
 5.00 601  
 5.05 611  
 5.10 621  
 5.15 631  
 5.20 641  
 5.25 651  
 5.30 661  
 5.35 671  
 5.40 681  
 5.45 691  
 5.50 701  
 5.55 711  
 6.00 721  
 6.05 731  
 6.10 741  
 6.15 751  
 6.20 761  
 6.25 771  
 6.30 781  
 6.35 791  
 6.40 801  
 6.45 811  
 6.50 821  
 6.55 831  
 7.00 841  
 7.05 851  
 7.10 861  
 7.15 871  
 7.20 881  
 7.25 891  
 7.30 901  
 7.35 911  
 7.40 921  
 7.45 931  
 7.50 941  
 7.55 951  
 8.00 961  
 8.05 971  
 8.10 981  
 8.15 991  
 8.20 1001  
 8.25 1011  
 8.30 1021  
 8.35 1031  
 8.40 1041  
 8.45 1051  
 8.50 1061  
 8.55 1071  
 8.60 1081  
 8.65 1091  
 8.70 1101  
 8.75 1111  
 8.80 1121  
 8.85 1131  
 8.90 1141  
 8.95 1151  
 9.00 1161  
 9.05 1171  
 9.10 1181

1.551300  
 10.001200  
 10.051210  
 10.101220  
 10.151230  
 10.201240  
 10.251250  
 10.301260  
 10.351270  
 10.401280  
 10.451290  
 10.501300  
 10.551310  
 11.001320  
 11.051330  
 11.101340  
 11.151350  
 11.201360  
 11.251370  
 11.301380  
 11.351390  
 11.401400  
 11.451410  
 11.501420  
 11.551430  
 12.001440  
 12.051450  
 12.101460  
 12.151470  
 12.201480  
 12.251490  
 12.301500  
 12.351510  
 12.401520  
 12.451530  
 12.501540  
 12.551550  
 13.001560  
 13.051570  
 13.101580  
 13.151590  
 13.201600  
 13.251610  
 13.301620  
 13.351630  
 13.401640  
 13.451650  
 13.501660  
 13.551670  
 14.001680  
 14.051690  
 14.101700  
 14.151710  
 14.201720  
 14.251730  
 14.301740  
 14.351750  
 14.401760  
 14.451770  
 14.501780  
 14.551790  
 15.001800



20.15243.	10
20.20254.	10
20.25265.	10
20.30276.	10
20.35287.	10
20.40298.	10
20.45309.	10
20.50320.	10
20.55331.	10
21.00342.	10
21.05353.	10
21.10364.	10
21.15375.	10
21.20386.	10
21.25397.	10
21.30408.	10
21.35419.	10
21.40430.	10
21.45441.	10
21.50452.	10
21.55463.	10
22.00474.	10
22.05485.	10
22.10496.	10
22.15507.	10
22.20518.	10
22.25529.	10
22.30540.	10
22.35551.	10
22.40562.	10
22.45573.	10
22.50584.	10
22.55595.	10
23.00606.	10
23.05617.	10
23.10628.	10
23.15639.	10
23.20650.	10
23.25661.	10
23.30672.	10
23.35683.	10
23.40694.	10
23.45705.	10
23.50716.	10
23.55727.	10
24.00738.	10

PLAN FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS -  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS									
				RATIO 1 .05	RATIO 2 .10	RATIO 3 .15	RATIO 4 .20	RATIO 5 .25	RATIO 6 .30	RATIO 7 .35	RATIO 8 .40	RATIO 9 .45	
HYDROGRAPH AT	000001	.90 2.33	1	322. ( 9.13)	645. ( 18.25)	967. ( 27.38)	1289. ( 36.51)	2256. ( 63.89)	3223. ( 91.27)	4190. ( 118.65)	5157. ( 146.03)	6446. ( 182.54)	
	000002	.90 2.33	1	16. ( .44)	32. ( .91)	52. ( 1.40)	67. ( 1.91)	98. ( 2.76)	127. ( 3.25)	1128. ( 31.95)	2294. ( 64.95)	4602. ( 130.31)	
HYDROGRAPH AT	000003	.21 .55	1	215. ( 6.10)	431. ( 12.19)	646. ( 18.29)	961. ( 24.39)	1507. ( 42.68)	2153. ( 60.97)	2799. ( 79.27)	3445. ( 97.56)	4307. ( 121.95)	
	COMBINED	1.11 2.89	1	223. ( 6.31)	446. ( 12.67)	669. ( 18.95)	892. ( 25.27)	1566. ( 44.35)	2230. ( 63.15)	2890. ( 81.82)	3548. ( 100.46)	5082. ( 143.91)	
PLUCCO TO	000004	1.11 2.89	1	4. ( .12)	9. ( .24)	16. ( .45)	24. ( .60)	47. ( 1.33)	91. ( 2.50)	553. ( 15.65)	1974. ( 55.89)	4305. ( 121.89)	

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1. RES. 10.345

RATIO OF PPE	MAXIMUM RESERVOIR W.S.-FT	ELEVATION STORAGE OUTFLOW	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TOP OF DAM		TIME OF FAILURE HOURS
							791.00	1240.	
							689.	109.	
							0.		
.05	784.91		0.00	753.	16.	0.00	19.00		0.00
.10	785.95		0.00	817.	32.	0.00	19.00		0.00
.15	786.81		0.00	881.	52.	0.00	18.92		0.00
.20	787.65		0.00	944.	67.	0.00	18.92		0.00
.35	789.08		0.00	1140.	98.	0.00	19.08		0.00
.50	791.90		.70	1321.	327.	7.00	18.67		0.00
.65	792.61		1.61	1395.	1128.	7.92	17.67		0.00
.80	794.07		2.07	1443.	2294.	8.25	16.67		0.00
1.00	793.62		2.62	1500.	4602.	8.83	16.33		0.00

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 RES: 10366

RATIO OF POT	MAXIMUM RESERVOIR W.S. ELEV	ELEVATION SIDRA OUTFLOW	INITIAL VALUE 753.40 84. 0.	SPILLWAY CREST 753.40 84. 0.	TOP OF DAM 756.80 445. 142.	DURATION OVER TOP HOURS	MAXIMUM OUTFLOW CFS	MAXIMUM STORAGE AC-FT	MAXIMUM DEPTH OVER DAM	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.05	753.65		0.00	111.	4.	0.00	24.00	0.00	0.00	0.00	0.00
.10	753.91		0.00	130.	9.	0.00	24.00	0.00	0.00	0.00	0.00
.15	754.10		0.00	167.	16.	0.00	24.00	0.00	0.00	0.00	0.00
.20	754.42		0.00	192.	24.	0.00	24.00	0.00	0.00	0.00	0.00
.35	755.03		0.00	257.	47.	0.00	24.00	0.00	0.00	0.00	0.00
.50	755.92		0.00	352.	91.	0.00	24.00	0.00	0.00	0.00	0.00
.65	757.25		.45	492.	553.	5.83	19.42	0.00	0.00	0.00	0.00
.80	757.59		.79	529.	1974.	7.25	17.75	0.00	0.00	0.00	0.00
1.00	757.85		1.05	556.	4305.	7.92	16.67	0.00	0.00	0.00	0.00